BRUHAT BANGALORE MAHANAGARA PALIKE

YELHANKA ZONE ELECTRICAL DIVISION

Office of the Executive Engineer
Electrical Division, Yelahanka Zone
Bruhath Bengaluru Mahanagara Palike

"Schedule B"

Name of Work:- Providing, laying and correcting Aerial Bunched Cables/damaged poles/panel boards to Telecom layout double road,via railway gate to MCHS layout double road in Ward No-6

Sl.No	Qty	Description Of Work	Unit	Quoted Rates	
				In figures	In words
1	5	Digging of Pits 1.8 mtr depth for errection of 9 to 10mtr Long Steel/RCC/PSC supports as per approved Drawing.Ordinary Soil	Nos	378.00	Rupees Three Hundred Seventy Eight Only
2	5	Erection of steel supports 9.0 to 10.00 mtr long such as 22.68 kg (50 lbs) Rail, 27.22 kg (60 Lbs) Rail IBeam of sizes 200x100mm, 175x90 mm, 125x100mm. Fabricates poles tubular poles in pits of 1.8 mtrDepth, Aligning, Refilling with soil and ramming asapproved drawing	Nos	304.00	Rupees Three Hundred Four Only
3	5	Pole concreting with CC 1:2:4 (without coping) f) 8mtrs support (400x400x1500mm)	Nos	982.00	Rupees Nine Hundred Eighty Two Only
4	5	Any Dismantling work 90% of the corresponding erection charges(304x90%=273.6)	Nos	250.00	Rupees Two Hundred Fifty Only
5	4	Transportation using 7.5/10 Tons Lorry Rs. 23 per Kms subjected to a minimum of Rs. 1200/-per day (shifting of Panel boards & Poles)	Nos	1200.00	Rupees One Thousand Two Hundred Only
6	1350	Supplying of 1.1KV grade Aerial Bunched Cable Stranded & Compacted Aluminum Phase Conductor, and Stranded Messenger Conductor with all aluminum Alloy, Phase Conductor is insulated with XLPE Compound, insulated Messenger with specified IS-14255:1995 & confirming to GTP of GROUP-A.2 X 25 + 1 X 25 SQ.MM KPWD ELE SR 2014-15	Per Mtr	113.00	Rupees One Hundred Thirteen Only
7	1350	Stringing of 1.1kv LT Arial Bunched Cable, BESCOM SR	Per Mtr	10.00	Rupees Ten Only
8	5	Piercing connector suitable for 16 sqmm - 95 sqmm AB cable -steel light connection. Bescom SR of 2010-11, Page no 16 of 34, Serial no 51.12.	Each	47.00	Rupees Forty Seven Only
9	5	Suspension clamp assembly 25 to 95 sqmm bare messenger. Bescom SR of 2010-11, Page no 16 of 34, Sl no 51.17.	Each	47.00	Rupees Forty Seven Only
10	4	Dead end clamp / Anchor clamp assembly 25 to 95 sqmm bare messenger, Bescom SR of 2010-11, Page no 16 o 34, Sl no 51.16.	Each	180.00	Rupees One Hundred Eighty Only
11	2	Universal Hook and Bolts and Nuts, Bescom SR of 2010-11, Page no 16 of 34, Sl no. 51.15.	Each	120.00	Rupees One Hundred Twenty Only
12	5	Erection of Suspension Clamp - 25 to 95 sqmm bare messenger. Bescom SR of 2010-11, Page No 21 of 27, Sl No 26.6.	Each	280.00	Rupees Two Hundred Eighty Only
13	5	Painting of existing street light pole after scrapping the old paint and painted with suitable colour enamel/Silver paint including coping/footing of the pole .8Mtr and above street light pole.	Nos	35.00	Rupees Thirty Five Only

For GANGA ENTERPRISES

Proprietor

14	2	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete. Protection of Overload and Short circuit with thermal Magnetic/Micro processor release and Earth Fault as per IS-13947. (Icu = Ics) THREE POLE 100Amps 25kA.26/5.14.1	Each	500.00	Rupees Five Hundred Only
15	80	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A.4 core 16 sqmm40/6.4.4	Mtrs	3530.00	Rupees Three Thousand Five Hundred Thirty Only
16	80	Labour charges for laying of 1.1 KV class UG cable when supplied agency in existing trench GI pipe / stoneware pipe / on wall /on pole as required. I. In existing trench/duct. 6 sqmm to 16 sqmm	Mtrs	110.00	Rupees One Hundred Ten Only
17	70	Digging of trench of 0.6 m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc.,complete.41/6.6.1	Mtrs	15.00	Rupees Fifteen Only
18	70000	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 7tanks treatment with powder coated paint and finally finished with approved colour etc., complete.16SWG KPWD ELE SR Page-30/5.42.2	sq.cms	45.00	Rupees Forty Five Only
19	100	Wiring for lighting/power circuit using one of PVC insulated 1100v grade, multis and Copper conductor single core cable in open or consealed system of wiring.I Group A Materials.6 sqmm 6/2.3.3	Mtrs	0.25	Rupees And Paise Twenty Five Only
20	2	Thiristor based single/ Three phase smart street light control and monitoring system Remotely control and and monitorable smart street light system by using web or mobile application .smart control system has hardware ruggedness over field issues like line cross, line short, lighting and any other irregularities in voltage. It has some features like 1.Remote lighting management.2.Precise lighting turnoff.3.Load ballancing.4.Load power regulation.5.Status tracking. It works on the basis of some of these features 1) Main Control Unit (Mother board) : Handles controlling , data handling and other communication process. 2) Communication unit: GSM/GPRS quad bandwith RS232 interface wireless communication unit 3) Gate Driver Unit: Firing angle controllable board for driving the thyristor 4) Switching Thyristor: SCR 110 AMPS dual thyristor modules for switching 5)Embedded Firmware: Firmware to control , handle , process the data and communicate it wirelessly.6) Metal Enclosure : IP66 weather prof metal enclosure. 7) transformers: Customized step down transformers for various purposes.8) Wiring and other device assembly components.	No	35200.00	Rupees Thirty Five Thousand Two Hundred Only

I am prepared to take up the above work at rates quoted in the Schedule 'B'

For GANGA ENTERPRISES

Proprietor

Contractor

EXECUTIVE ENGINEER (ELEC)
BBMP, Yelahanka Zone